

SEPA Environmental Checklist

Purpose of checklist

Governmental agencies use this checklist to help determine whether the environmental impacts of your proposal are significant. This information is also helpful to determine if available avoidance, minimization, or compensatory mitigation measures will address the probable significant impacts or if an environmental impact statement will be prepared to further analyze the proposal.

Instructions for applicants

This environmental checklist asks you to describe some basic information about your proposal. Please answer each question accurately and carefully, to the best of your knowledge. You may need to consult with an agency specialist or private consultant for some questions. **You may use “not applicable” or “does not apply” only when you can explain why it does not apply and not when the answer is unknown.** You may also attach or incorporate by reference additional studies reports. Complete and accurate answers to these questions often avoid delays with the SEPA process as well as later in the decision-making process.

The checklist questions apply to **all parts of your proposal**, even if you plan to do them over a period of time or on different parcels of land. Attach any additional information that will help describe your proposal or its environmental effects. The agency to which you submit this checklist may ask you to explain your answers or provide additional information reasonably related to determining if there may be significant adverse impact.

Instructions for lead agencies

Please adjust the format of this template as needed. Additional information may be necessary to evaluate the existing environment, all interrelated aspects of the proposal and an analysis of adverse impacts. The checklist is considered the first but not necessarily the only source of information needed to make an adequate threshold determination. Once a threshold determination is made, the lead agency is responsible for the completeness and accuracy of the checklist and other supporting documents.

Use of checklist for nonproject proposals

For nonproject proposals (such as ordinances, regulations, plans and programs), complete the applicable parts of sections A and B, plus the Supplemental Sheet for Nonproject Actions (Part D). Please completely answer all questions that apply and note that the words "project," "applicant," and "property or site" should be read as "proposal," "proponent," and "affected geographic area," respectively. The lead agency may exclude (for non-projects) questions in Part B: Environmental Elements that do not contribute meaningfully to the analysis of the proposal.

A. Background

1. Name of proposed project, if applicable:

Bremerton School District Consolidated Facilities project

2. Name of applicant:

Bremerton School District

3. Address and phone number of applicant and contact person:

Applicant:

Bremerton School District, Dr. Garth Steedman
Assistant Superintendent of Finance, Operations, and Human Resources
134 Marion Avenue North
Bremerton, WA 98312
garth.steedman@bremertonschools.org

Contact Person:

David McBride, OAC Services
2200 1st Ave S Ste 200
Seattle, WA 98134
360-473-8299
david.mcbride@consertus.com

4. Date checklist prepared:

January 20, 2026

5. Agency requesting checklist:

Bremerton School District

6. Proposed timing of schedule (including phasing, if applicable):

Construction is proposed to start in Summer 2026 and proposed completion is Summer 2027.

7. Do you have any plans for future additions, expansion, or further activity related to or connected with this proposal? If yes, explain.

There are no plans for future additions or phases associated with this proposal.

8. List any environmental information you know about that has been prepared, or will be prepared, directly related to this proposal.

Prepared:

- Critical Areas Technical Memorandum prepared by Grette Associates dated April 10, 2025
- Cultural Resources Assessment prepared by Drayton Archaeology dated May 5, 2025
- Traffic Impact Assessment prepared by PH Consulting, dated June 25, 2025
- Geotechnical Report prepared by Krazan Associates, Inc. dated May 15, 2025

- Grading and Paving Plan prepared by Coughlin Porter Lundeen, dated October 1, 2025
- Hazardous Building Materials Survey prepared by Krazan & Associates, Inc. dated February 11, 2025
- Hazardous Building Materials Survey Addendum Letter 1 prepared by Krazan & Associates, Inc. dated December 16, 2025
- DAHP EZ-1 Form

To be prepared:

- Temporary Erosion and Sediment Control Plan (TESC)
- Topographic Survey
- Architectural Plans
- Landscape Plans
- Civil Plans
- Photometrics Analysis
- Drainage Report

9. Do you know whether applications are pending for governmental approvals of other proposals directly affecting the property covered by your proposal? If yes, explain.

There are no known projects pending governmental approval affecting this proposal.

10. List any government approvals or permits that will be needed for your proposal, if known.

City of Bremerton:

Demolition Permits

Building and Site Development Permits

Commercial Site Plan Review

Department of Archaeology and Historic Preservation:

EZ-21-02 Review

Ecology:

General Construction Stormwater Permit

11. Give brief, complete description of your proposal, including the proposed uses and the size of the project and site. There are several questions later in this checklist that ask you to describe certain aspects of your proposal. You do not need to repeat those answers on this page. (Lead agencies may modify this form to include additional specific information on project description.)

Existing Site

The project site is located at 200 Bruenn Avenue and 5520 Burwell Street Bremerton, WA 98310, on parcel 3826-000-002-0004. The project site is approximately 3.4 acres and contains an existing approximately 30,673 SF main building and one approximately 2,400 SF storage building. The main building was built in 1942 and a second prefabricated metal support structure was likely constructed in the late 1970s. Currently, school buses access

the property via Bruenn Avenue and facilities vehicles access the property via Burwell Street.

Proposed Project

The proposal is for the replacement of the Bremerton School District facilities building on the same site. The proposal includes construction of a one-story building totaling approximately 18,000 SF. This building has two key areas, the main office space and the high-bay warehouse and maintenance space. The main office space is approximately 13,000 SF and contains offices, training spaces, conference rooms, and technical shops. The high-bay warehouse and vehicle maintenance space is approximately 5,000 SF and contains a mezzanine level for additional storage. A bus wash space will be adjacent to the building on the south end but will not be contained under the building envelope. This building will be constructed prior to demolition of the existing main building. The approximately 2,400 SF storage building is proposed to remain. The proposal also includes staff and bus parking stalls and a new stormwater detention system.

The project proposes to change the current circulation pattern, with school buses and facility vehicles proposed to access the site via Bruenn Avenue and exit the site via Burwell Street. During construction, buses, drivers, and dispatch employees will be relocated to a temporary facility while the new building is under construction. The existing maintenance staff will remain in the existing building while the new building is being constructed. Once the new building is constructed, the maintenance staff will move to the new building, and the existing building will be demolished. The proposed project will staff approximately 50 employees. The existing facility staffs approximately 43 employees, for a total increase of approximately seven employees due to the integration of the IT department into the new facility.

- 12. Location of the proposal. Give sufficient information for a person to understand the precise location of your proposed project, including a street address, if any, and section, township, and range, if known. If a proposal would occur over a range of area, provide the range or boundaries of the site(s). Provide a legal description, site plan, vicinity map, and topographic map, if reasonably available. While you should submit any plans required by the agency, you are not required to duplicate maps or detailed plans submitted with any permit applications related to this checklist.**

The project site is located at 200 Bruenn Avenue and 5520 Burwell Street Bremerton, WA 98310, on parcel 3826-000-002-0004 (Section 16, Township 24, Range 1E (SE/4)).

Legal Description: RESULTANT PARCEL B OF BOUNDARY LINE ADJUSTMENT RECORDED UNDER AUDITOR'S FILE NO. 9401130009, BEING 2, PLAT OF QUALHEIM, ACCORDING TO THE PLAT RECORDED IN VOLUME 27 OF PLATS, PAGES 30 AND 31, RECORDS OF KITSAP COUNTY, WASHINGTON; EXCEPT THAT PORTION DESCRIBED AS FOLLOWS: COMMENCING AT THE SOUTHEAST CORNER OF SAID LOT 2; THENCE NORTH 0°23'10 EAST ALONG THE EAST LINE THEREOF 143.62 FEET; THENCE SOUTH 89°46'48 WEST 69.99 FEET TO THE TRUE POINT OF BEGINNING; THENCE SOUTH 89°46'48 WEST 6.43 FEET; THENCE NORTH 0°39'50 WEST 186.65 FEET TO THE NORTH LINE OF LOT 2; THENCE NORTH 89°46'48 EAST ALONG

Vicinity Map



1. Earth

Per the Geotechnical Report prepared by Krazan & Associates, Inc. dated May 15, 2025, the site is relatively flat.

b. What is the steepest slope on the site (approximate percent slope)?

Page 5

- c. **What general types of soils are found on the site (for example, clay, sand, gravel, peat, muck)? If you know the classification of agricultural soils, specify them, and note any agricultural land of long-term commercial significance and whether the proposal results in removing any of these soils.**

Per the Geotechnical Report prepared by Krazan & Associates, Inc. dated May 15, 2025, the Natural Resources Conservation Services map indicates that the site soils are mainly classified as Alderwood gravelly sandy loam (0-8 percent slopes). Soils encountered at the site during field investigation included the following:

- A superficial layer of asphaltic concrete or crushed rock (depth of approximately three inches)
- Undocumented fill consisting of brownish red, sandy silt, brown, silt with gravel, and brown to dark gray, silty sand with gravel (depths of approximately three to ten feet)
- Moist, medium dense to very dense, gray to brown silty sand with varying amounts of gravel, sand with silt and varying amounts of gravel, and wet, hard, brown to gray sandy silt (depths of 22.5 to 26.5 feet).

- d. **Are there surface indications or history of unstable soils in the immediate vicinity? If so, describe.**

There are no known indications of unstable soils on the project site or in the immediate vicinity.

- e. **Describe the purpose, type, total area, and approximate quantities and total affected area of any filling, excavation, and grading proposed. Indicate source of fill.**

The proposal requires approximately 8,000 cubic yards of cut and 7,500 cubic yards of fill for the total project, for a net cut of 500 cubic yards. Excess excavated materials would be removed from the site and transported to an approved stockpile site. Imported fill material will be transported from an approved location. The total disturbed area on the site will be approximately 3.4 acres.

- f. **Could erosion occur because of clearing, construction, or use? If so, generally describe.**

Erosion could occur during construction activities associated with grading, filling, and excavating. To minimize potential erosion impacts, a Temporary Erosion Control Plan (TESC) will be prepared as part of the site development plans for each phase of development. The TESC will include construction procedures and best management practices.

- g. **About what percent of the site will be covered with impervious surfaces after project construction (for example, asphalt or buildings)?**

The existing site impervious area is approximately 74 percent, and the impervious surface area anticipated for the proposed project is 74 percent (or approximately 2.50 acres). No increase or decrease in impervious surface amounts are proposed.

h. Proposed measures to reduce or control erosion, or other impacts to the earth, if any.

The Geotechnical Report prepared by Krazan & Associates, Inc. dated May 15, 2025, concluded that soil erosion can be minimized by limiting the amount of stripped soil areas exposed during construction activities frequently wetting the surface soils during construction, and with proper landscaping of the site following completion of construction. Erosion potential may also be mitigated by the use of temporary erosion control measures, such as silt fences, hay bales, straw wattles, mulching, control ditches or diversion trenching, and contour furrowing. The walls of excavations should be covered with plastic sheeting or other erosion control surfacing during periods of rainfall.

2. Air

a. What types of emissions to the air would result from the proposal during construction, operation, and maintenance when the project is completed? If any, generally describe and give approximate quantities if known.

Construction activities have the potential to create temporary dust emissions during earth-moving activities and exhaust emissions due to the combustion of gasoline and diesel fuels. Dust and exhaust emissions are expected to be minimal, localized, and temporary. After construction, no additional emissions to air are anticipated to result from the proposal.

Additionally, demolition activities may cause the release of asbestos-containing materials, the handling of which is described in the Limited Hazardous Materials Survey prepared by Krazan Associates, Inc. dated February 11, 2025, with an addendum prepared on December 16, 2025.

b. Are there any off-site sources of emissions or odor that may affect your proposal? If so, generally describe.

There are no known off-site air emissions or odors that may impact the proposal.

c. Proposed measures to reduce or control emissions or other impacts to air, if any:

During construction temporary measures will be applied where necessary, which may include limiting the idling of construction equipment, water sprays to control dust, limiting vehicle speeds, and general maintenance of construction equipment. All proposed demolition practices will be handled in accordance with the federal, state, and local regulations.

3. Water

a. Surface:

1. Is there any surface water body on or in the immediate vicinity of the site (including year-round and seasonal streams, saltwater, lakes, ponds, wetlands)? If

yes, describe type and provide names. If appropriate, state what stream or river it flows into.

Per the Critical Areas Report Memo prepared by Grette Associates dated April 10, 2025, there are no indications of potential wetland conditions within 300 feet of the subject property.

- 2. Will the project require any work over, in, or adjacent to (within 200 feet) the described waters? If yes, please describe and attach available plans.**

No, the proposal will not require any work over, in, or adjacent to the described waters.

- 3. Estimate the amount of fill and dredge material that would be placed in or removed from surface water or wetlands and indicate the area of the site that would be affected. Indicate the source of fill material.**

No fill or dredge material will be placed in or removed from surface water.

- 4. Will the proposal require surface water withdrawals or diversions? Give a general description, purpose, and approximate quantities if known.**

No, surface waters will not be withdrawn or diverted as a result of this proposal.

- 5. Does the proposal lie within a 100-year floodplain? If so, note location on the site plan.**

No, the site is not within a 100-year floodplain per FEMA firm panel 53035C0360F, effective date 2/3/2017.

- 6. Does the proposal involve any discharges of waste materials to surface waters? If so, describe the type of waste and anticipated volume of discharge.**

No, the proposal does not involve any discharges of waste materials to surface waters.

b. Ground:

- 1. Will groundwater be withdrawn from a well for drinking water or other purposes? If so, give a general description of the well, proposed uses and approximate quantities withdrawn from the well. Will water be discharged to groundwater? Give a general description, purpose, and approximate quantities if known.**

No groundwater will be withdrawn nor will stormwater runoff or water from irrigation or other sources be discharged to groundwater.

- 2. Describe waste material that will be discharged into the ground from septic tanks or other sources, if any (domestic sewage; industrial, containing the following chemicals...; agricultural; etc.). Describe the general size of the system, the number**

of such systems, the number of houses to be served (if applicable), or the number of animals or humans the system(s) are expected to serve.

There will be no waste material discharged into the ground as a result of this proposal.

c. Water Runoff (including stormwater):

- 1. Describe the source of runoff (including storm water) and method of collection and disposal, if any (include quantities, if known). Where will this water flow? Will this water flow into other waters? If so, describe.**

Within a small area located on the western portion of the site, runoff from building roofs, parking areas, sidewalks, and landscaped areas will be collected in a series of catch basins or other drainage collection elements and conveyed via storm drainage pipes to a new flow control facility, with a live storage volume of approximately 67,000 CF, designed per City of Bremerton's stormwater standards. Pollution generating surfaces will be routed to approved water quality treatment systems. The new stormwater detention system will discharge to the public storm system located on 1st Street. A small portion of the southwest corner of the existing site discharges to the public storm system on Bruenn Avenue. Based on preliminary designs, this portion of the site will remain undisturbed and will continue to discharge to Bruenn Avenue. The northern access drive flows to an offsite detention system and then to the public storm system on Burwell Street. No development is anticipated for this portion of the site, so the stormwater system will remain the same.

- 2. Could waste materials enter ground or surface waters? If so, generally describe.**

No waste materials will enter ground or surface waters as a result of this proposal.

- 3. Does the proposal alter or otherwise affect drainage patterns in the vicinity of the site? If so, describe.**

The proposal will not alter or affect drainage patterns on site or in the immediate vicinity.

- d. Proposed measures to reduce or control surface, ground, and runoff water, and drainage pattern impacts, if any:**

No measures proposed, as no impacts to runoff or drainage patterns are anticipated. The stormwater detention system will be designed to meet the requirements of the City of Bremerton's current stormwater manual.

4. Plants

- a. Check the types of vegetation found on the site:**

☒ **deciduous tree: alder, maple, aspen, other**

☒ **evergreen tree: fir, cedar, pine, other**

- ☒ shrubs
- ☒ grass
- ☐ pasture
- ☐ crop or grain
- ☐ orchards, vineyards, or other permanent crops.
- ☐ wet soil plants: cattail, buttercup, bullrush, skunk cabbage, other
- ☐ water plants: water lily, eelgrass, milfoil, other
- ☐ other types of vegetation

b. What kind and amount of vegetation will be removed or altered?

The existing site contains minimal vegetation and therefore the proposal does not require the removal of existing vegetation. Landscape plans will be prepared as a part of this proposal.

c. List threatened and endangered species known to be on or near the site.

There are no threatened or endangered plant species on the site or in the immediate vicinity.

d. Proposed landscaping, use of native plants, or other measures to preserve or enhance vegetation on the site, if any.

Landscape plans will be prepared as a part of this proposal. Landscaping is proposed along the southern and northern perimeters of the project site.

e. List all noxious weeds and invasive species known to be on or near the site.

There are no known noxious weeds or invasive plant species on the site or in the vicinity.

5. Animals

a. List any birds and other animals that have been observed on or near the site or are known to be on or near the site.

Examples include:

- Birds: hawk, heron, eagle, songbirds, other:
- Mammals: deer, bear, elk, beaver, other: small mammals
- Fish: bass, salmon, trout, herring, shellfish, other:

b. List any threatened and endangered species known to be on or near the site.

Per the Washington Department of Fish and Wildlife (WDFW), there are no threatened or endangered animal species on the site or in the immediate vicinity.

c. Is the site part of a migration route? If so, explain.

The Puget Sound Region is within the Pacific Flyway, a bird migration route.

d. Proposed measures to preserve or enhance wildlife, if any.

None proposed, as the proposal will not impact wildlife.

e. List any invasive animal species known to be on or near the site.

There are no known invasive animal species on the site or in the vicinity.

6. Energy and natural resources

a. What kinds of energy (electric, natural gas, oil, wood stove, solar) will be used to meet the completed project's energy needs? Describe whether it will be used for heating, manufacturing, etc.

The project will require electricity for all daily operations, including lighting and heating.

b. Would your project affect the potential use of solar energy by adjacent properties? If so, generally describe.

No, the proposal will not impact the use of solar energy by adjacent properties.

c. What kinds of energy conservation features are included in the plans of this proposal? List other proposed measures to reduce or control energy impacts, if any.

The construction and operation of the new building will conform to the applicable portions of the Washington Energy Code. Energy efficient methods will be used for the mechanical and lighting systems. The on-site lighting will include the use of LED fixtures.

7. Environmental health

a. Are there any environmental health hazards, including exposure to toxic chemicals, risk of fire and explosion, spill, or hazardous waste, that could occur because of this proposal? If so, describe.

Environmental health hazards, including exposure to toxic materials, could occur in the demolition and excavation phase of this project. During construction accidental spills of hazardous materials from demolition, equipment and vehicles could occur. A spill prevention and control plan will be developed to prevent the accidental release of contaminants into the environment.

A Limited Hazardous Materials Survey was prepared by Krazan Associates, Inc. dated February 11, 2025, with an addendum prepared on December 16, 2025. If asbestos-containing materials are discovered, they are required to be removed and disposed of in accordance with Washington State regulations. If lead-based paint is discovered, all lead-based materials that may be disturbed as a natural part of renovation and/or demolition are required to be removed and disposed of in accordance with Washington State regulations. If material coated with lead-based paint are disposed of during demolition, some or all of the debris may be subject to the disposal requirements of Federal, State, and local laws.

1. Describe any known or possible contamination at the site from present or past uses.

There is no known contamination at the site. Per the Department of Ecology “What’s in My Neighborhood: Toxics Cleanup” mapping, there are six cleanup sites within 0.25 miles of the site, with the following statuses:

- Carnation Dairy Bremerton (CSID 10718) – No Further Action
- ADCo (CSID 11653) - No Further Action
- Pacific Pride Fuel Facility (CSID 9395) - Cleanup Started
- Jemco Insulation Inc (CSID 5355) - No Further Action
- Auto Center Boulevard (CSID 3241) - Cleanup Started
- Hoover Motors (CSID 12601) - No Further Action

2. Describe existing hazardous chemicals/conditions that might affect project development and design. This includes underground hazardous liquid and gas transmission pipelines located within the project area and in the vicinity.

Per the National Pipeline Public Mapping System, there are no hazardous liquid or gas transmission pipelines on site or within the vicinity of the site.

3. Describe any toxic or hazardous chemicals that might be stored, used, or produced during the project's development or construction, or at any time during the operating life of the project.

The proposal does not involve the storage or use of toxic or hazardous chemicals.

4. Describe special emergency services that might be required.

No additional special emergency services will be required other than those normally provided such as police, emergency medical, and fire protection.

5. Proposed measures to reduce or control environmental health hazards, if any.

Hazardous building materials will be removed safely from the site pursuant to applicable regulatory requirements. Any soils contaminated by spills would be excavated and disposed of in a manner consistent with the level of contamination and in accordance with federal, state, and local regulatory requirements. A Limited Hazardous Materials Survey has been prepared by Krazan Associates, Inc. dated February 11, 2025, with an addendum prepared on December 16, 2025, as a part of this proposal.

b. Noise

1. What types of noise exist in the area which may affect your project (for example: traffic, equipment, operation, other)?

No existing noise on or near the site will impact the proposal.

2. What types and levels of noise would be created by or associated with the project on a short-term or a long-term basis (for example: traffic, construction, operation, other)? Indicate what hours noise would come from the site)?

Temporary, short-term noise impacts typical of construction projects will occur with operation of equipment during construction. Construction will normally occur between the hours of 7:00 a.m. and 6:00 p.m.

Additional sources of noise will be consistent with existing conditions, including vehicular traffic. All noise generated from the project will be below the allowable limits of WAC 173-60.

3. Proposed measures to reduce or control noise impacts, if any:

To mitigate general noise impacts during construction, measures will include locating stationary equipment away from receiving properties, turning off idling construction equipment, requiring contractors to maintain all equipment, and training construction crews to avoid unnecessarily loud actions near residential areas. No measures are proposed for noise following the completion of the project, as the proposed use is the same as the existing use and is not anticipated to result in noise impacts.

8. Land and shoreline use

a. What is the current use of the site and adjacent properties? Will the proposal affect current land uses on nearby or adjacent properties? If so, describe.

The current use of the site is the Bremerton School District Maintenance Facility, which is the same as the proposed use. North of the site are commercial/auto uses, east and west are commercial/light industrial/manufacturing uses, and south are car wash/commercial/light industrial/manufacturing uses. The proposal will not impact adjacent land uses, as the proposed use is the same as the existing and is compatible with surrounding uses.

b. Has the project site been used as working farmlands or working forest lands? If so, describe. How much agricultural or forest land of long-term commercial significance will be converted to other uses because of the proposal, if any? If resource lands have not been designated, how many acres in farmland or forest land tax status will be converted to nonfarm or nonforest use?

The subject property has not recently been used as working farm or forest lands.

1. Will the proposal affect or be affected by surrounding working farm or forest land normal business operations, such as oversize equipment access, the application of pesticides, tilling, and harvesting? If so, how?

No, the proposal will not affect or be affected by surrounding working farm or forest operations.

c. Describe any structures on the site.

There is an approximately 30,673 SF maintenance facility building and an approximately 2,400 SF storage building currently on-site.

d. Will any structures be demolished? If so, what?

The existing main building (approximately 30,673 SF) will be demolished. Both existing buildings will remain while the new building is being constructed. Once the new building is constructed, the existing main building will be demolished, but the storage building will remain.

e. What is the current zoning classification of the site?

The site is zoned Freeway Corridor (FC).

f. What is the current comprehensive plan designation of the site?

The current land use designation of the site is Freeway Corridor (FC).

g. If applicable, what is the current shoreline master program designation of the site?

The site is not located within shoreline designation.

h. Has any part of the site been classified as a critical area by the city or county? If so, specify.

Per the Critical Areas Report Memo prepared by Grette Associates dated April 10, 2025, there are no indications of potential wetland conditions within 300 feet of the subject property.

Per the Kitsap County GIS mapping system, there are no critical areas identified within the project site or immediate vicinity.

i. Approximately how many people would reside or work in the completed project?

The proposed project will staff approximately 50 employees. The existing facility staffs approximately 43 employees, for a total increase of approximately 7 employees due to the integration of the District's Information Technology (IT) department into the new facility.

j. Approximately how many people would the completed project displace?

The project will not result in the displacement of people. During construction, the buses that are currently stored on the project site, the bus drivers, and dispatch employees will be relocated to a temporary facility while the new building is under construction. The existing maintenance staff will remain in the existing building while the new building is being constructed. Once the new building is constructed, all staff will move to the new building, and the existing building will be demolished.

k. Proposed measures to avoid or reduce displacement impacts, if any.

No specific measures are proposed as the proposal would not result in displacement.

l. Proposed measures to ensure the proposal is compatible with existing and projected land uses and plans, if any.

None proposed, as the proposal is for the same use as existing and will be compatible with adjacent land uses.

m. Proposed measures to reduce or control impacts to agricultural and forest lands of long-term commercial significance, if any:

None proposed, as the proposal will not impact agricultural and forest lands.

9. Housing

- a. **Approximately how many units would be provided, if any? Indicate whether high, middle, or low-income housing.**
None, the proposal does not include any housing.
- b. **Approximately how many units, if any, would be eliminated? Indicate whether high, middle, or low-income housing.**
None, the proposal will not impact housing.
- c. **Proposed measures to reduce or control housing impacts, if any:**
None, the proposal will not impact housing.

10. Aesthetics

- a. **What is the tallest height of any proposed structure(s), not including antennas; what is the principal exterior building material(s) proposed?**
The proposed main building will be the tallest proposed structure and will be approximately 28 feet in height.
- b. **What views in the immediate vicinity would be altered or obstructed?**
No views will be altered or obstructed by this proposal.
- c. **Proposed measures to reduce or control aesthetic impacts, if any:**
None proposed, as no aesthetic impacts are anticipated.

11. Light and glare

- a. **What type of light or glare will the proposal produce? What time of day would it mainly occur?**
The proposal will produce similar levels of light or glare that is currently produced, as the proposed use is the same as the existing. A lighting plan will be prepared as a part of this proposal.
- b. **Could light or glare from the finished project be a safety hazard or interfere with views?**
No safety hazards are expected due to light or glare from this proposal.
- c. **What existing off-site sources of light or glare may affect your proposal?**
No off-site sources of light or glare are expected to impact the proposal.
- d. **Proposed measures to reduce or control light and glare impacts, if any:**
Lighting fixtures will be LED, full cutoff type and shielded to prevent light spillage to adjacent properties.

12. Recreation

- a. **What designated and informal recreational opportunities are in the immediate vicinity?**

The project site and immediate vicinity does not provide any recreational opportunities, as adjacent uses are primarily commercial/industrial/and manufacturing uses.

- b. **Would the proposed project displace any existing recreational uses? If so, describe.**

The proposal will not result in the displacement of any existing recreational uses.

- c. **Proposed measures to reduce or control impacts on recreation, including recreation opportunities to be provided by the project or applicant, if any:**

None proposed as no impacts to recreation are anticipated.

13. Historic and cultural preservation

- a. **Are there any buildings, structures, or sites, located on or near the site that are over 45 years old listed in or eligible for listing in national, state, or local preservation registers? If so, specifically describe.**

There are no properties listed on the site or in the vicinity, per the Washington State Department of Archaeology and Historic Preservation (DAHP) Washington Information System for Architectural and Archaeological Records Data (WISAARD) mapping. Per the Cultural Resources Report prepared by Drayton Archaeology dated May 5, 2025, the project site contains a building built in 1942, along with a prefabricated metal support structure likely constructed in the late 1970s. Drayton recommended that both buildings be found not eligible for listing in the National Register of Historic Places.

Per the Cultural Resources Report, the following buildings and sites are located within a 1-mile radius of the project site:

- One NRHP-eligible property located approximately 0.70 miles north of the project area (45KP138), which is a historic log cabin constructed in 1906.
- One historic site (45KP147) located approximately 0.16 miles northeast of the project site, which is a historic military camp. Cultural material associated with the site consists of military structures, civilian structures, historic roads, and historic debris.

- b. **Are there any landmarks, features, or other evidence of Indian or historic use or occupation? This may include human burials or old cemeteries. Are there any material evidence, artifacts, or areas of cultural importance on or near the site? Please list any professional studies conducted at the site to identify such resources.**

There are no properties listed as “determined eligible” on the site or in the vicinity, per the Washington State Department of Archaeology and Historic Preservation (DAHP) Washington Information System for Architectural and Archaeological Records Data (WISAARD) mapping. Per the WISAARD mapping, a majority of the site is mapped a four out of five (survey highly advised – high risk for risk of discovery of archaeological

resources). The western perimeter of the site is mapped a three out of five (survey recommended – moderate risk for risk of discovery of archaeological resources).

Per the Cultural Resources Report prepared by Drayton Archaeology dated May 5, 2025, the following cemeteries are located within a 1-mile radius of the site:

- Forest Lawn Cemetery - located approximately 0.24 miles northwest of the project site. The cemetery was added in 1931 as an expansion to the Lewis Funeral Chapel, which was built in 1912. The chapel and cemetery are still in use today.
- Woodlawn Memorial Park - is located approximately 0.41 miles northwest of the project site. The cemetery was originally established in 1928 with the construction of the Miller-Reynolds Funeral Home. In 1940, Woodlawn Memorial Park was developed and in 1970 the two cemeteries merged into Woodlawn-Miller Memorial Park.

No cultural materials were observed during field investigation of the project site.

- c. Describe the methods used to assess the potential impacts to cultural and historic resources on or near the project site. Examples include consultation with tribes and the department of archeology and historic preservation, archaeological surveys, historic maps, GIS data, etc.**

The proposal utilized the Washington Information System for Architectural and Archaeological Records Data (WISAARD) online database to assess potential impacts to cultural and historic resources on and near the project site.

The Cultural Resources Report prepared by Drayton Archaeology dated May 5, 2025 consisted of a field investigation including detailed visual survey of the existing ground disturbance and location of cultural materials or structure, and subsurface examination of soils through the use of shovel probes. Drayton's field investigation was conducted on April 23, 2025.

- d. Proposed measures to avoid, minimize, or compensate for loss, changes to, and disturbance to resources. Please include plans for the above and any permits that may be required.**

The project also underwent Executive Order (EO) 21-02 review, which is separate from SEPA, but requires consultation between BSD and DAHP and Affected Tribes regarding potential impacts to archaeological resources and historic buildings and structures. DAHP concluded on January 12, 2026 that no historic resources will be impacted by the current project as proposed and no further contact with DAHP is necessary at this time.

No disturbance to cultural or historical resources is expected during construction and archaeological oversight is not anticipated or recommended as a result of the field investigation. The contractor shall implement an Inadvertent Discovery Plan following the protocols outlined in the Drayton Cultural Resources Report. The Washington State Department of Archaeology and Historic Preservation will be notified if any cultural or archeological objects are found during the site development work. If cultural or

archaeological resources are found, then all site work will stop until Washington State Department of Archaeology and Historic Preservation provides guidance.

14. Transportation

- a. Identify public streets and highways serving the site or affected geographic area and describe proposed access to the existing street system. Show on site plans, if any.**

Currently, school buses access the property via Bruenn Avenue and facilities vehicles access the property via Burwell Street. The project proposes to change the current circulation pattern, with school buses and facility vehicles proposed to access the site via Bruenn Avenue and exit the site via Burwell Street.

- a. Is the site or affected geographic area currently served by public transit? If so, generally describe. If not, what is the approximate distance to the nearest transit stop?**

The site is served by Kitsap Transit with the closest bus stops located along Auto Center Way, approximately 0.1 miles east of the school site. The bus stops located nearest to the project site are served by Route 220 – Sunn Fjord and Route 228 - Marion. Route 228 operates Monday through Friday, from 5am to 7:30pm. Route 220 operates Monday through Friday, from 4:30am to 9pm.

- b. Will the proposal require any new or improvements to existing roads, streets, pedestrian, bicycle, or state transportation facilities, not including driveways? If so, generally describe (indicate whether public or private).**

No, the proposal does not require improvements to existing roads. The project proposes maintaining the existing access points to the project site from Burwell Street and Bruenn Avenue.

- c. Will the project or proposal use (or occur in the immediate vicinity of) water, rail, or air transportation? If so, generally describe.**

No, the project is not within the vicinity of water, rail, or air transportation.

- d. How many vehicular trips per day would be generated by the completed project or proposal? If known, indicate when peak volumes would occur and what percentage of the volume would be trucks (such as commercial and nonpassenger vehicles). What data or transportation models were used to make these estimates?**

Per the Traffic Impact Analysis prepared by PH Consulting dated June 25, 2025, the project is forecast to generate approximately 400 vehicle trips per day, consistent with the existing trips. The addition of 7 staff could increase the trip generation by 7 trips during the peak hours (in or out). Peak hour volumes occur between 1-2 PM and approximately 44% of the peak hour volumes is forecast to be made up of heavy vehicles (school buses). The volumes were forecast based on driveway volumes collected during the morning, midday, and afternoon peak hours, consistent with ITE methodology, and information provided by the Applicant about future programming.

- e. **Will the proposal interfere with, affect, or be affected by the movement of agricultural and forest products on roads or streets in the area? If so, generally describe.**

No, the proposal will not affect or be affected by the movement of agricultural or forest products.

- f. **Proposed measures to reduce or control transportation impacts, if any:**

None proposed, as the project is not forecasted to generate additional new trips.

15. Public services

- a. **Would the project result in an increased need for public services (for example: fire protection, police protection, public transit, health care, schools, other)? If so, generally describe.**

The project will not result in an increased need for public services other than those already provided at the site.

- b. **Proposed measures to reduce or control direct impacts on public services, if any.**

No proposed measures as the proposal is not likely to result in impacts on public service.

16. Utilities

- a. **Circle utilities currently available at the site:** ☐ electricity, ☐ natural gas, ☐ water, ☐ refuse service, ☐ telephone, ☐ sanitary sewer, septic system, other:

- b. **Describe the utilities that are proposed for the project, the utility providing the service, and the general construction activities on the site or in the immediate vicinity which might be needed.**

Electricity: Puget Sound Energy

Natural gas: Cascade Natural Gas

Water and Sewer: City of Bremerton

Refuse: Waste Management Northwest

Telephone: Comcast

C. Signature

The above answers are true and complete to the best of my knowledge. I understand that the lead agency is relying on them to make its decision.

X *Anisa Thaci*

Type name of signee: Anisa Thaci

Position and agency/organization: AHBL, Inc.

Date submitted: January 26, 2026